



4143 W Orleans Street
 McHenry, IL 60050
 815-344-0678
 www.alternatepowerinc.com

Estimate

Date	Estimate #
11/6/2017	10142

Name / Address
City of Rochelle Fire Dept. Lt. David W Sawlsville 401 5th Ave Rochelle, IL 61068

Terms	Rep
50% down, 50% du...	MJH

Description	Qty	Rate	Total
Blue Star 60 kW Natural Gas Generator Set. EPA Certified, WPE with sound insulation foam. 208V Three Phase. General Motors 5.7L EPA 60kW Standby Power Rating at 1800 RPM Fuel System: Natural Gas Fuel System Options: Dry Fuel Strainer Engine Model: General Motors 5.7L EPA 60kW Standby Power Rating at 1800 RPM Governor - Electronic Isochronous Voltage: 208/120V 3 Phase 60 Hz 0.8 PF Gen Model: Marathon 361CSL1602 12 Lead Wired 208V 3 Phase Low Wye 130°C Rise Over 27°C Ambient Voltage Regulator: Marathon PM300 Automatic Voltage Regulator with PMG Excitation Control Panel: Blue Star DGC-2020 Microprocessor Based Gen-Set Controller Mounted Facing Left from Generator End (Unless Specified Otherwise) Standard Features: Low Oil Pressure, High Coolant Temp, Overspeed, Overcrank Shutdowns Emergency Stop Pushbutton, Audible Alarm Buzzer with Silencing Switch Optional Features Include: Generator Protection (Undervoltage, Overvoltage, Underfrequency, Overfrequency, Overcurrent) Control Panel Options: Voltage Adjust Rheostat (Switch) - Panel Mounted Low Water Level Sensor with Shutdown Remote Annunciator: RDP-110 Remote Annunciator Panel (Surface Mounted) Unit Color: Tan Enclosure: Level 2 (Weather Proof Enclosure with Foam) Powder Coated .090 Aluminum Rugged and Durable 150 MPH Wind Rated Enclosure Pitched Roof for Increased Structural Integrity and Improved Watershed Punched Intake with Baffle and Punched Exhaust Openings Keyed Alike Lockable Doors with Draw Down Latches and Stainless Steel Component Hinges		26,069.04	26,069.04

Use of Visa or MasterCard is subject to a 4% convenience charge passed on to us.	Sales Tax (0.0%)
--	-------------------------

Payment Terms: 50% Deposit upon acceptance of Estimate Balance due upon delivery/job completion	Total
--	--------------

Any deviation from the above specifications due to unforeseen circumstances and involving extra costs will be executed upon customer approval and the costs will become an extra charge over and above the estimate. All elements of this agreement are contingent upon strikes, accidents, inclement weather or delays beyond our control. Orders placed with manufacturer are not refundable. Prices quoted are good for 30 days. Alternate Power Industries maintains a security interest in the above equipment and reserves the right afforded to secured parties under the Uniform Commercial Code, to remedy any default of payment through collection procedures and/or removal of collateral from premises with or without process of law and without breach of peace. Such procedures and cost, legal and otherwise will be at customer's expense.

Signature _____

Date _____



4143 W Orleans Street
 McHenry, IL 60050
 815-344-0678
 www.alternatepowerinc.com

Estimate

Date	Estimate #
11/6/2017	10142

Name / Address
City of Rochelle Fire Dept. Lt. David W Sawlsville 401 5th Ave Rochelle, IL 61068

Terms	Rep
50% down, 50% du...	MJH

Description	Qty	Rate	Total
Additional 1.5" Thick Polydamp Type D Acoustical Foam (PAF) Formed Steel Base with Mounting and Lifting Holes Includes Vibration Mounts to Isolate Unit from Base Rail Sound Attenuation Foam: Sound Attenuation Installed in Enclosure Cooling: Unit Mounted Radiator (50°C Ambient) Oil Drain Extension: Plumbed to Bulkhead Fitting in Base Mainline Breaker: 200 Amp 3 Pole 240 Volt Breaker Mounted & Wired in a NEMA 1 Enclosure Jacket Water Heater: Engine Block Heater 1500W 120VAC Rated for -20°F Heater Installed with Isolation Valves and Wired to Terminal Air Cleaner: Dry Single Stage Silencer: Critical Grade Compact (CPJ Series) Silencer Mounted to Engine Battery: 12 Volt System with Rack and Cables Battery Charger: 12 Volt 6 Amp Mounted and Wired to Terminal Factory Test: Standard Commercial Testing Includes: Verification of Alarm Shutdowns, Voltage Settings, Block Loading to Rated kWe and PF Owner's Manual: Print Copy (Qty 1), Flash Drive (Qty 1) Warranty: 5 Year / 3000 Hour Comprehensive Payment Terms: Due Upon on Receipt Lead Time: 12-14 Weeks			
Use of Visa or MasterCard is subject to a 4% convenience charge passed on to us.	Sales Tax (0.0%)		
Payment Terms: 50% Deposit upon acceptance of Estimate Balance due upon delivery/job completion	Total		

Any deviation from the above specifications due to unforeseen circumstances and involving extra costs will be executed upon customer approval and the costs will become an extra charge over and above the estimate. All elements of this agreement are contingent upon strikes, accidents, inclement weather or delays beyond our control. Orders placed with manufacturer are not refundable. Prices quoted are good for 30 days. Alternate Power Industries maintains a security interest in the above equipment and reserves the right afforded to secured parties under the Uniform Commercial Code, to remedy any default of payment through collection procedures and/or removal of collateral from premises with or without process of law and without breach of peace. Such procedures and cost, legal and otherwise will be at customer's expense.

Signature _____

Date _____



4143 W Orleans Street
 McHenry, IL 60050
 815-344-0678
 www.alternatepowerinc.com

Estimate

Date	Estimate #
11/6/2017	10142

Name / Address
City of Rochelle Fire Dept. Lt. David W Sawlsville 401 5th Ave Rochelle, IL 61068

Terms	Rep
50% down, 50% du...	MJH

Description	Qty	Rate	Total
Generator Freight from Distributor		1,200.00	1,200.00
ASCO 300 Series ATS		5,780.00	5,780.00
Series: 300 Volts: 208/120V 3 PH			
Service Entrance Rated Yes Poles 3			
Amps 400 Enclosure Nema 1			
Warranty:			
Two (2) Year Basic ATS Limited Warranty Standard			
Optional Accessories:			
ATS Freight from Distributor		250.00	250.00
Use of Visa or MasterCard is subject to a 4% convenience charge passed on to us.	Sales Tax (0.0%)		
Payment Terms: 50% Deposit upon acceptance of Estimate Balance due upon delivery/job completion	Total		

Any deviation from the above specifications due to unforeseen circumstances and involving extra costs will be executed upon customer approval and the costs will become an extra charge over and above the estimate. All elements of this agreement are contingent upon strikes, accidents, inclement weather or delays beyond our control. Orders placed with manufacturer are not refundable. Prices quoted are good for 30 days. Alternate Power Industries maintains a security interest in the above equipment and reserves the right afforded to secured parties under the Uniform Commercial Code, to remedy any default of payment through collection procedures and/or removal of collateral from premises with or without process of law and without breach of peace. Such procedures and cost, legal and otherwise will be at customer's expense.

Signature _____

Date _____



4143 W Orleans Street
 McHenry, IL 60050
 815-344-0678
 www.alternatepowerinc.com

Estimate

Date	Estimate #
11/6/2017	10142

Name / Address
City of Rochelle Fire Dept. Lt. David W Sawlsville 401 5th Ave Rochelle, IL 61068

Terms	Rep
50% down, 50% du...	MJH

Description	Qty	Rate	Total
<p>Installation of all electrical and gas connections to generator and automatic transfer switch.</p> <p>The generator will be placed on the existing cement pad nearest to the northwest corner of the Fire Department building. The Automatic Transfer Switch will be located nearest to the incoming electrical service on the north/west wall. All electrical connections will be made and terminated in this area. A remote annunciator panel will be installed and piped from the generator into the garage bay of the building. Actual location will be determined during installation.</p> <p>The gas service will be upgraded by NICOR and a meter will be installed outside the building near the northeast corner. Details of the upgrade to be given by NICOR. NICOR will be covering the costs of this upgrade. We will tap directly off the new gas meter and run the gas line outside the building along the north wall to the generator. If location of the proposed meter is changed by NICOR engineers, we may then run the gas line through the HVAC room, up through the ceiling/stairs, into the garage bay, across the north wall, out to the generator. The building and/or appliances may have to be regulated back down to 1/4" pressure.</p> <p>Factory Authorized Start-Up Testing and Warranty Initialization by Certified Technician</p>		12,000.00	12,000.00
		1,000.00	1,000.00
Use of Visa or MasterCard is subject to a 4% convenience charge passed on to us.	Sales Tax (0.0%)		\$0.00
Payment Terms: 50% Deposit upon acceptance of Estimate Balance due upon delivery/job completion	Total		\$46,299.04

Any deviation from the above specifications due to unforeseen circumstances and involving extra costs will be executed upon customer approval and the costs will become an extra charge over and above the estimate. All elements of this agreement are contingent upon strikes, accidents, inclement weather or delays beyond our control. Orders placed with manufacturer are not refundable. Prices quoted are good for 30 days. Alternate Power Industries maintains a security interest in the above equipment and reserves the right afforded to secured parties under the Uniform Commercial Code, to remedy any default of payment through collection procedures and/or removal of collateral from premises with or without process of law and without breach of peace. Such procedures and cost, legal and otherwise will be at customer's expense.

Signature _____

Date _____