

ENEL GREEN POWER

# ROCHELLE II SOLAR PROJECT

CITY OF ROCHELLE, ILLINOIS

## LANDSCAPING PLAN

### DEVELOPMENT TEAM

#### DEVELOPER

ENEL GREEN POWER NORTH AMERICA  
100 BRICKSTONE SQUARE, SUITE 300  
ANDOVER, MA 01810  
PHONE: (978) 681-1900  
CONTACT: CURTIS HUDSON

#### CONSULTANT

ATWELL, LLC  
TWO TOWNE SQUARE, SUITE 700  
SOUTHFIELD, MI 48076  
PHONE: (248) 447-2000  
FAX: (248) 447-2001  
CONTACT: JARED HICKS, PE

### GOVERNING AGENCIES

#### CITY OF ROCHELLE

815-562-6161  
420 NORTH 6TH STREET  
ROCHELLE, IL 61068

### FLOODPLAIN NOTE

PER THE CURRENT EFFECTIVE FLOOD INSURANCE RATE MAPS FOR THIS AREA, THE PROJECT FLOODPLAIN STATUS IS:

- ZONE X - AREA OF MINIMAL FLOOD HAZARD
- ZONE AE - SPECIAL FLOOD HAZARD AREA (WITH BASE FLOOD ELEVATION (BFE) OR DEPTH

MAPS REFERENCED: 17141C03483E EFF. 8/17/2016

### NOTES

1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH GOVERNING AGENCY STANDARDS.
2. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ALL FRANCHISE UTILITY (GAS, ELECTRIC, DATA) CONSTRUCTION, REMOVAL, AND RELOCATIONS. ANY FRANCHISE UTILITY INFORMATION ON THESE PLANS IS SHOWN FOR REFERENCE ONLY.

### PROJECT NARRATIVE

THE PROPOSED SITE WILL CONSIST OF A SOLAR ARRAY, ASSOCIATED ELECTRICAL EQUIPMENT, RELATED ACCESS DRIVES, PERIMETER FENCE, AND LANDSCAPING, ON 0-PLUS ACRES, IN THE CITY OF ROCHELLE, IL.

### REQUIRED PERMITS

AS PER CITY OF ROCHELLE REQUIREMENTS.

### LEGAL DESCRIPTION

PART OF THE NORTHEAST QUARTER AND PART OF THE NORTHWEST FRACTIONAL QUARTER OF SECTION 18, TOWNSHIP 40 NORTH, RANGE 2 EAST OF THE THIRD PRINCIPAL MERIDIAN, BOUNDED AND DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF THE NORTHWEST FRACTIONAL QUARTER OF SAID SECTION 18; THENCE NORTH 88 DEGREES 10 MINUTES 52 SECONDS EAST (GRID BEARING BASED ON THE ILLINOIS WEST STATE PLANE COORDINATE SYSTEM) ALONG THE NORTH LINE OF SAID NORTHWEST FRACTIONAL QUARTER, A DISTANCE OF 417.42 FEET TO THE POINT OF BEGINNING OF THE HERINAFTER DESCRIBED TRACT OF LAND; THENCE SOUTH 01 DEGREES 37 MINUTES 09 SECONDS EAST PARALLEL WITH THE WEST LINE OF SAID NORTHWEST FRACTIONAL QUARTER, A DISTANCE OF 417.42 FEET; THENCE SOUTH 88 DEGREES 10 MINUTES 52 SECONDS WEST PARALLEL WITH THE NORTH LINE OF SAID NORTHWEST FRACTIONAL QUARTER, A DISTANCE OF 402.42 FEET TO A POINT 15 FEET EAST OF, AS MEASURED PERPENDICULAR TO THE WEST LINE OF SAID NORTHWEST FRACTIONAL QUARTER; THENCE SOUTH 01 DEGREES 37 MINUTES 09 SECONDS EAST PARALLEL WITH SAID WEST LINE, A DISTANCE OF 2206.17 FEET TO THE SOUTH LINE OF SAID NORTHWEST FRACTIONAL QUARTER; THENCE NORTH 88 DEGREES 24 MINUTES 32 SECONDS EAST ALONG SAID SOUTH LINE AND THE SOUTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 18, A DISTANCE OF 1682.48 FEET TO A POINT, SAID POINT BEING 25.00 FEET WEST FROM THE EAST LINE OF THE WEST 13 1/3 RODS OF SAID NORTHEAST QUARTER; THENCE NORTH 01 DEGREES 24 MINUTES 33 SECONDS WEST, PARALLEL WITH THE WEST LINE OF SAID NORTHEAST QUARTER, A DISTANCE OF 1604.20 FEET; THENCE SOUTH 88 DEGREES 10 MINUTES 56 SECONDS WEST, A DISTANCE OF 275.00 FEET; THENCE NORTH 01 DEGREES 24 MINUTES 33 SECONDS WEST PARALLEL WITH THE WEST LINE OF SAID NORTHEAST QUARTER, A DISTANCE OF 1026.02 FEET TO A POINT ON THE NORTH LINE OF THE NORTHWEST FRACTIONAL QUARTER OF SAID SECTION 18, SAID POINT BEING 79.99 FEET WEST OF THE NORTHEAST CORNER OF SAID NORTHWEST FRACTIONAL QUARTER; AND THENCE SOUTH 88 DEGREES 10 MINUTES 52 SECONDS WEST ALONG SAID NORTH LINE, A DISTANCE OF 1014.71 FEET TO THE POINT OF BEGINNING, CONTAINING 91.42 ACRES, MORE OR LESS, ALL SITUATED IN THE TOWNSHIP OF DEMENT, THE COUNTY OF OGLE, AND THE STATE OF ILLINOIS.

### SHEET INDEX


C-000	COVER SHEET
C-100	EXISTING SITE AND BMP LOCATIONS PLAN
C-101	SOIL EROSION AND SEDIMENTATION CONTROL NOTES AND DETAILS
C-102	SOIL EROSION AND SEDIMENTATION CONTROL NOTES AND DETAILS
C-200	PROPOSED SITE PLAN
C-201	SITE PLAN NOTES AND DETAILS
C-300	PROPOSED GRADING AND DRAINAGE PLAN
C-301	GRADING AND DRAINAGE NOTES, AND TABLES
C-400	PROPOSED LANDSCAPING PLAN
C-401	LANDSCAPING NOTES AND DETAILS
C-500	STANDARD DETAILS

### APPLICABLE CODES/STANDARDS

CITY OF ROCHELLE MUNICIPAL CODE  
2015 INTERNATIONAL BUILDING CODE  
2015 INTERNATIONAL FIRE CODE  
2015 INTERNATIONAL MECHANICAL CODE  
2018 INTERNATIONAL ENERGY CONSERVATION CODE  
2018 ILLINOIS ACCESSIBILITY CODE  
2014 NATIONAL ELECTRICAL CODE


### 9-1-1 ADDRESS

416 NORTH 6TH STREET  
ROCHELLE, IL




STATE OF ILLINOIS

NOT TO SCALE



OLGE COUNTY

NOT TO SCALE



VICINITY MAP

SCALE: 1" = 2000'



Know what's below.

Call before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE: CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL, LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL, LLC.

ATWELL  
866.850.4200 www.atwell-group.com



ROCHELLE II SOLAR PROJECT  
COVER SHEET  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS



CLIENT


DATE 04/12/2021

REV A ISSUED FOR REVIEW  
REV B REISSUED FOR REVIEW  
REV C ISSUED FOR VARIANCE  
REV D ISSUED FOR VARIANCE

REVISIONS  
SCALE 0 XX XXXX  
AS NOTED  
DR. SPB | CH. SPB  
P.M. LFC  
BOOK --  
JOB 20004665  
SHEET NO.

C-000

CAD FILE: 20004665-C-000.DWG



**EXISTING SITE AND  
BMP LOCATIONS PLAN**  
SCALE: 1" = 100'-0"




Know what's below.

**Call before you dig.**  
THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE MANNER ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE CONTRACTOR. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

**NOTICE:**  
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES OR OF ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.

**ATWELL**  
866.850.4200 [www.atwell-group.com](http://www.atwell-group.com)  
3100 W. WISCONSIN AVE. SUITE 101  
ANN ARBOR, MI 48104  
734.934.4000



ROCHELLE II SOLAR PROJECT  
EXISTING SITE AND BMP LOCATIONS PLAN  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS



CLIENT  
DATE 04/14/2021

REV A ISSUED FOR REVIEW  
REV B ISSUED FOR REVIEW  
REV C ISSUED FOR VARIANCE  
REV D ISSUED FOR VARIANCE

REVISIONS

NO.	DATE	DESCRIPTION

SCALE 0 50 100  
1" = 100'-0"  
DR. SPB CH. SPB  
P.M. JFC  
BOOK --  
JOB 20004665  
SHEET NO. C-100

CAD FILE: 20004665-C-100.DWG

LEGEND	
	PROJECT SITE
	MINOR TOPO
	MAJOR TOPO
	RIVERS/STREAMS
	100 YEAR FLOOD PLAIN
	EXISTING TRANSMISSION
	PROPOSED SILT FENCE
	PROPOSED SILT SOX
	SLOPE/FLOW DIRECTION
	SITE/CONSTRUCTION ENTRANCE

**EXISTING SITE PLAN NOTES**

- EXISTING BACKGROUND DATA IS BASED ON THE FOLLOWING: HORIZONTAL DATUM IS BASED ON ILLINOIS STATE PLANE WEST, FIPS 1202, US FEET (GRID) AND WAS ESTABLISHED BY O.P.U.S. OBSERVATIONS IN ACCORDANCE WITH THE NATIONAL GEODETIC SURVEY'S SPECIFICATION FOR O.P.U.S. OBSERVATIONS; VERTICAL DATUM IS BASED ON NAVD 88.
- THE EXISTING SITE IS PRIMARILY USED AS ROW CROPS WITH TYPE HSG B AND B/D SOILS. THE SITE GENERALLY DRAINS FROM THE NORTH TO SOUTH WITH AN APPROXIMATE SLOPE OF 0 TO 1 PERCENT. THERE ARE NO WELL-DEFINED DRAINAGE AREAS CROSSING THE PROJECT BOUNDARY, ALTHOUGH THE KYLE RIVER RUNS NORTH TO SOUTH, JUST WEST OF THE PROJECT BOUNDARY.
- FROM A REVIEW OF AERIAL PHOTOS FOR THE PROJECT SITE, IT APPEARS THAT THERE IS A SUBSURFACE DRAINAGE SYSTEM ACROSS THE SITE. NO RECORD DRAWINGS WERE LOCATED TO VERIFY THE LOCATION OR SIZE OF THE DRAINAGE SYSTEM.
- A FEMA FLOODPLAIN IS PRESENT ON A PORTION OF THE PROJECT SITE. THE SITE IS COVERED BY FEMA FIRM PANEL 17141C0483E. THIS FLOODPLAIN IS IDENTIFIED AS A FEMA FLOOD ZONE "AE". FEMA FLOOD ZONE "AE" HAS A 1% ANNUAL CHANCE OF FLOODING, ALSO KNOWN AS THE 100-YEAR FLOOD PLAIN. MAJORITY OF THE SITE IS IDENTIFIED AS FEMA FLOOD ZONE "X". THIS ZONE HAS A MINIMAL FLOOD HAZARD.
- STORM WATER MANAGEMENT, BEST MANAGEMENT PRACTICES SHALL BE EMPLOYED TO MINIMIZE EROSION AND SEDIMENTATION DURING CONSTRUCTION OF THE SOLAR FARM.

**CONSTRUCTION SEQUENCE SCHEDULE**

- INSTALLATION OF SOIL EROSION AND SEDIMENT CONTROL SE/SC MEASURES
  - INSTALL STABILIZED CONSTRUCTION ENTRANCE WITH PROPOSED CULVERT AND OUTLET PROTECTION (IF REQUIRED).
  - INSTALL EROSION CONTROL BARRIER
- CONTAIN STOCKPILE LOCATIONS WITHIN SITE AND INSTALL EROSION CONTROL MEASURES AS NECESSARY.
- INSTALL CHIP AND SEAL COATED ACCESS DRIVES.
- START CONSTRUCTION OF SOLAR PANELS AND UTILITIES.
- INITIATE TEMPORARY SEEDING WITHIN ONE BUSINESS DAY OF INACTIVITY, THROUGHOUT CONSTRUCTION, INCLUDING AREAS THAT WILL BE INACTIVE FOR 14 DAYS OR MORE.
- REMOVE GRAVEL FOR LAYDOWN AREA, AND SPREAD WITH TOPSOIL AND SEED.
- PERMANENTLY STABILIZE ALL AREAS.
- REMOVE ALL TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES AFTER THE SITE IS STABILIZED WITH VEGETATION.
  - SOIL EROSION AND SEDIMENT CONTROL MAINTENANCE MUST OCCUR EVERY WEEK AND WITHIN 24 HOURS OF THE END OF A STORM OR BY THE END OF THE FOLLOWING BUSINESS DAY AFTER EVERY 0.5 IN. OR GREATER RAINFALL EVENT.

**CONTRACTOR CERTIFICATION**

I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (LRI01) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

GENERAL CONTRACTOR NAME \_\_\_\_\_

GENERAL CONTRACTOR ADDRESS \_\_\_\_\_

GENERAL CONTRACTOR TELEPHONE \_\_\_\_\_

GENERAL CONTRACTOR SIGNATURE \_\_\_\_\_

DATE \_\_\_\_\_

SITE ADDRESS \_\_\_\_\_

SUBCONTRACTOR NAME \_\_\_\_\_

SUBCONTRACTOR ADDRESS \_\_\_\_\_

SUBCONTRACTOR TELEPHONE \_\_\_\_\_

SUBCONTRACTOR SIGNATURE \_\_\_\_\_

DATE \_\_\_\_\_


**OWNER CERTIFICATION**

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED, BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.

OWNER DATE \_\_\_\_\_

**GENERAL EROSION CONTROL AND SEDIMENTATION NOTES**

- AN EROSION CONTROL BARRIER SHALL BE INSTALLED AS INDICATED IN THE PLAN PRIOR TO THE COMMENCEMENT OF DEMOLITION OR CONSTRUCTION OPERATIONS.
- CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL MEASURES DURING ENTIRE CONSTRUCTION PERIOD.
- ANY SEDIMENT TRACKED ONTO PUBLIC RIGHT-OF-WAYS SHALL BE SWEEPED AT THE END OF EACH WORKING DAY.
- ALL STOCKPILE AREAS SHALL BE LOCATED WITHIN LIMIT OF WORK LINE AND STABILIZED TO PREVENT EROSION.
- ALL DEBRIS GENERATED DURING SITE PREPARATION ACTIVITIES SHALL BE LEGALLY DISPOSED OF OFF-SITE.
- SITE ELEMENTS TO REMAIN MUST BE PROTECTED FOR DURATION OF PROJECT.
- ALL TOPSOIL ENCOUNTERED AND/OR DISTURBED WITHIN THE LIMITS OF THE PROPOSED CHIP AND SEAL COATED ACCESS DRIVES, EQUIPMENT AREAS, ETC., SHALL BE STRIPPED AS NEEDED AND STOCKPILED FOR REUSE. EXCESS TOPSOIL SHALL BE DISPOSED OF ON SITE AS DIRECTED BY OWNER. TOPSOIL PILES SHALL REMAIN SEGREGATED FROM EXCAVATED SUBSURFACE SOIL MATERIALS.
- ADDITIONAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED AS CONDITIONS WARRANT OR AS DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE.
- ALL POINTS OF CONSTRUCTION EGRESS OR INGRESS SHALL BE MAINTAINED TO PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADS.
- TEMPORARY DIVERSION DITCHES, PERMANENT DITCHES, CHANNELS, EMBANKMENTS AND ANY DENUDED SURFACE WHICH WILL BE EXPOSED FOR AN EXTENDED PERIOD OF TIME SHALL BE STABILIZED AS REQUIRED.
- SOIL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED AND MAINTAINED ON A DAILY BASIS DURING CONSTRUCTION TO ENSURE THAT CHANNELS, DITCHES AND PIPES ARE CLEAR OF DEBRIS AND THAT THE EROSION CONTROL BARRIERS ARE INTACT.
- DUST SHALL BE CONTROLLED AS NEEDED BY SPRINKLING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE OWNER OR REPRESENTATIVE.
- CARE SHALL BE EXERCISED SO AS TO PREVENT ANY UNSUITABLE MATERIAL FROM MIGRATING OUTSIDE THE LIMIT OF WORK.
- ADDITIONAL EROSION CONTROL SHALL BE LOCATED AS CONDITIONS WARRANT OR AS DIRECTED BY THE OWNER OR REPRESENTATIVE.
- CLEAN AND MAINTAIN EROSION CONTROL BARRIER AS REQUIRED DURING CONSTRUCTION OPERATIONS TO ENSURE ITS CONTINUED FUNCTIONALITY.
- OVERALL SITE DEVELOPMENT WILL MAINTAIN EXISTING TOPOGRAPHY AND STORM WATER DRAINAGE PATTERNS.
- THE OVERALL DEVELOPMENT WILL BE RE-SEED TO DEVELOP A PERMANENT VEGETATIVE COVER AS INDICATED ON THE LANDSCAPE PLAN. COVER CROP OR OTHER TEMPORARY STABILIZATION WILL BE IMPLEMENTED IN THE INTERIM.
- NO CONSTRUCTION ACTIVITIES, AS PART OF THE SITE DEVELOPMENT, SHALL OCCUR WITHIN ANY DELINEATED WETLANDS OR WETLAND BUFFERS, AS REQUIRED BY THE ILLINOIS DEPARTMENT OF NATURAL RESOURCES.
- ALL EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED IN ACCORDANCE WITH THE CONDITIONS OF APPLICABLE IL GENERAL NPDES PERMIT.
- THE CONTRACTOR SHALL CONTROL WASTES, GARBAGE, DEBRIS, WASTEWATER, AND OTHER SUBSTANCES ON THE SITE IN SUCH A MANNER THAT THEY SHALL NOT BE TRANSPORTED FROM THE SITE BY THE ACTION OF WINDS, STORM WATER RUNOFF, OR OTHER FORCES. PROPER DISPOSAL OR MANAGEMENT OF ALL WASTES AND UNUSED BUILDING MATERIAL, APPROPRIATE TO THE NATURE OF THE WASTE OR MATERIAL IS REQUIRED. COMPLIANCE IS REQUIRED WITH ALL STATE OR LOCAL REGULATIONS REGARDING WASTE DISPOSAL, SANITARY SEWER, OR SEPTIC SYSTEMS.
- ALL DISCHARGES FROM DEWATERING ACTIVITIES, INCLUDING DISCHARGES FROM DEWATERING OF TRENCHES AND EXCAVATIONS, SHALL BE MANAGED BY APPROPRIATE CONTROLS.
  - DEWATERING DISCHARGES SHALL BE TREATED OR CONTROLLED TO MINIMIZE DISCHARGES OF POLLUTANTS.
  - THE DISCHARGE SHALL NOT INCLUDE VISIBLE FLOATING SOLIDS OR FOAM.
  - AN OIL-WATER SEPARATOR OR SUITABLE FILTRATION DEVICE SHALL BE USED TO TREAT OIL, GREASE, OR OTHER SIMILAR PRODUCTS IF DEWATERING IS FOUND TO CONTAIN THESE MATERIALS.
  - TO THE EXTENT FEASIBLE, USE VEGETATED, UPLAND AREAS OF THE SITE TO INFILTRATE DEWATERING WATER BEFORE DISCHARGE.
  - BACKWASH WATER (WATER USED TO BACKWASH/CLEAN ANY FILTERS USED AS PART OF THE STORMWATER TREATMENT) MUST BE PROPERLY TREATED OR HAULED OFF-SITE FOR DISPOSAL.
  - DEWATERING TREATMENT DEVICES SHALL BE PROPERLY MAINTAINED.
- GENERAL CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA, EMPLOYEE PARKING AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES.
- ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR DISPOSED.
- SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- EXCEPT AS PREVENTED BY INCLEMENT WEATHER CONDITIONS, STABILIZATION OF DISTURBED AREAS MUST BE INITIATED WITHIN ONE (1) WORKING DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES AND SHALL BE COMPLETED AS SOON AS POSSIBLE, BUT NO LATER THAN 14 DAYS FROM THE INITIATION OF THE STABILIZATION WORK IN AN AREA.
- THIS EROSION CONTROL PLAN SHALL BE IMPLEMENTED ON ALL DISTURBED AREAS WITHIN THE CONSTRUCTION SITE. ALL MEASURES INVOLVING EROSION CONTROL PRACTICES SHALL BE INSTALLED UNDER THE GUIDANCE OF QUALIFIED PERSONNEL EXPERIENCED IN EROSION CONTROL, AND FOLLOWING THE PLANS AND SPECIFICATIONS INCLUDED HEREIN.
- ALL DISTURBED AREAS, AREAS USED FOR STORAGE OR MATERIALS THAT ARE EXPOSED TO PRECIPITATION, AND ALL AREAS WHERE STORMWATER TYPICALLY FLOWS WITHIN THE SITE SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE STILL STABILIZED. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF SITE SEDIMENT TRACKING.
- CONTRACTOR SHALL TAKE CORRECTIVE ACTIONS TO ADDRESS ANY STORMWATER CONTROL THAT NEEDS REPAIR OR REPLACEMENT AS SOON AS POSSIBLE AND DOCUMENT CORRECTIVE ACTIONS WITHIN SEVEN DAYS IN AN INSPECTION REPORT.
- CONTRACTOR SHALL INSTALL EROSION CONTROL BLANKET PER MANUFACTURER'S RECOMMENDATIONS ON ALL SLOPES 4:1 OR STEEPER.
- EXISTING VEGETATION SHALL BE PROTECTED AS MUCH AS PRACTICAL.
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE REMOVED AND DISPOSED OF WITHIN THIRTY DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY PRACTICES ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION.
- THIS EROSION CONTROL PLAN MUST BE RETAINED ON-SITE AT ALL TIMES DURING THE PERIOD OF CONSTRUCTION.




**MAINTENANCE (SILT FENCE)**

SILT FENCE SHALL BE REMOVED ONCE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED. SILT FENCE SHALL BE INSPECTED NO LESS FREQUENTLY THAN EVERY WEEK DURING CONSTRUCTION. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USEFUL LIFE AND THE FENCE STILL IS NECESSARY, THE FABRIC OR THE ENTIRE SYSTEM SHALL BE REPLACED PROMPTLY. SEDIMENT DEPOSITS MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF THE SILT FENCE. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, A SEEDBED PREPARED AND THE SITE VEGETATED.


**MAINTENANCE (SILT SOCKS)**

INSPECT AND MAINTAIN SILT SOCKS IN GOOD CONDITION. MAINTAIN THE INTEGRITY OF THE CONTROL, INCLUDING KEEPING THE BAGS FREE OF ACCUMULATED SILT, DEBRIS, ETC., UNTIL PERMANENT EROSION CONTROL FEATURES ARE IN PLACE, OR THE DISTURBED AREA HAS BEEN ADEQUATELY STABILIZED. STABILIZE THE AREAS DAMAGED BY THE REMOVAL PROCESS USING APPROPRIATE METHODS AS APPROVED. REPAIR OR REPLACE DAMAGED SILT SOCKS AS REQUIRED AND AS DIRECTED. TEMPORARILY REMOVE AND REPLACE SILT SOCKS AS REQUIRED TO FACILITATE WORK. REMOVE SEDIMENT AND DEBRIS WHEN ACCUMULATION AFFECTS THE PERFORMANCE OF THE DEVICES, AFTER A RAIN, AND WHEN DIRECTED. DISPOSE OF SEDIMENT AND DEBRIS AT AN APPROVED SITE IN A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.



- NOTES:**
- Temporary sediment fence shall be installed prior to any grading work in the area to be protected. They shall be maintained throughout the construction period and removed in conjunction with the final grading and site stabilization.
  - Filter fabric shall meet the requirements of material specification 592 Geotextile Table 1 or 2, Class with equivalent opening size of at least 30 for nonwoven and 40 for woven.
  - Fence posts shall be either standard steel post or wood post with a minimum cross-sectional area of 3.0 sq. in.

**EROSION CONTROL BLANKET - CHANNEL INSTALLATION**



**MAINTENANCE**

INSPECT ALL EROSION CONTROL BLANKETS PERIODICALLY AND AFTER RAINSTORMS TO CHECK FOR DAMAGE DUE TO WATER RUNNING UNDER THE BLANKET OR IF THE BLANKETS THAT HAVE BEEN DISPLACED BY WIND. ANY AREAS WHERE WATER SEEPED UNDER THE BLANKET, MORE STAPLES MAY BE NEEDED PER GIVEN AREA OR MORE FREQUENT ANCHORING TRENCHES INSTALLED WITH BETTER COMPACTION. IF SIGNIFICANT EROSION HAS OCCURRED UNDER THE BLANKET THEN GRADING AND RESEEDING MAY ALSO BE NECESSARY. ANY EROSION CONTROL BLANKETS THAT HAVE BEEN DISPLACED WILL NEED TO BE REINSTALLED AND RE-STAPLED. THIS MAY INDICATE THAT THE WRONG TYPE OF BLANKET WAS CHOSEN. ONE MAY NEED TO REVISIT THE SITE CHARACTERISTICS AND THEN SELECT A DIFFERENT TYPE OF EROSION CONTROL BLANKET OR CHOOSE A DIFFERENT PRACTICE.

**811**  
Know what's below.  
Call before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:  
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.

**ATWELL**  
www.atwell-group.com  
666.850.4200  
3100 W. WISCONSIN AVE. SUITE 200  
ROCHELLE, IL 60142  
734.934.4000

ROCHELLE II SOLAR PROJECT  
SOIL EROSION AND SEDIMENTATION CONTROL NOTES AND DETAILS  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS

**Green Power**

CLIENT: \_\_\_\_\_  
 DATE: 04/14/2021

REV A ISSUED FOR REVIEW  
 REV B ISSUED FOR REVIEW  
 REV C ISSUED FOR VARIANCE  
 REV D ISSUED FOR VARIANCE

REVISIONS

SCALE 0 XX XXX  
 AS NOTED

DR. SPB | CH. SPB  
 P.M. JFC  
 BOOK ---  
 JOB 20004665  
 SHEET NO. \_\_\_\_\_

C-101

**CONCRETE WASHOUT**

**INSTALLATION**

PREFABRICATED WASHOUT SYSTEMS/CONTAINERS

1. INSTALL AND LOCATE ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.


DESIGNED AND INSTALLED SYSTEMS

- UTILIZE AND FOLLOW THE DESIGN IN THE STORM WATER POLLUTION PREVENTION PLAN TO INSTALL THE SYSTEM.
- DEPENDENT UPON THE TYPE OF SYSTEM, EITHER EXCAVATE THE PIT OR INSTALL THE CONTAINMENT SYSTEM.
- A BASE SHALL BE CONSTRUCTED AND PREPARED THAT IS FREE OF ROCKS AND OTHER DEBRIS THAT MAY CAUSE TEARS OR PUNCTURES IN THE POLYETHYLENE LINING.
- INSTALL THE POLYETHYLENE LINING. FOR EXCAVATED SYSTEMS, THE LINING SHOULD EXTEND OVER THE ENTIRE EXCAVATION. THE LINING FOR BERMED SYSTEMS SHOULD BE INSTALLED OVER THE POOLING AREA WITH ENOUGH MATERIAL TO EXTEND THE LINING OVER THE BERM OR CONTAINMENT SYSTEM. THE LINING SHOULD BE SECURED WITH PINS, STAPLES, OR OTHER FASTENERS.
- PLACE FLAGS, SAFETY FENCING, OR EQUIVALENT TO PROVIDE A BARRIER TO CONSTRUCTION EQUIPMENT AND OTHER TRAFFIC.
- PLACE A NON-COLLAPSING, NON-WATER HOLDING COVER OVER THE WASHOUT FACILITY PRIOR TO A PREDICTED RAINFALL EVENT TO PREVENT ACCUMULATION OF WATER AND POSSIBLE OVERFLOW OF THE SYSTEM (OPTIONAL).
- INSTALL SIGNAGE THAT IDENTIFIES CONCRETE WASHOUT AREAS.
- POST SIGNS DIRECTING CONTRACTORS AND SUPPLIERS TO DESIGNATED LOCATIONS.
- WHERE NECESSARY, PROVIDE STABLE INGRESS AND EGRESS (SEE TEMPORARY CONSTRUCTION INGRESS/EGRESS PAD) OR ALTERNATIVE APPROACH PAD FOR CONCRETE WASHOUT SYSTEMS.

**MAINTENANCE**

- INSPECT DAILY AND AFTER EACH STORM EVENT.
- INSPECT THE INTEGRITY OF THE OVERALL STRUCTURE INCLUDING, WHERE APPLICABLE, THE CONTAINMENT SYSTEM.
- INSPECT THE SYSTEM FOR LEAKS, SPILLS, AND TRACKING OF SOIL BY EQUIPMENT.
- INSPECT THE POLYETHYLENE LINING FOR FAILURE, INCLUDING TEARS AND PUNCTURES.
- ONCE CONCRETE WASTES HARDEN, REMOVE AND DISPOSE OF THE MATERIAL.
- EXCESS CONCRETE SHOULD BE REMOVED WHEN THE WASHOUT SYSTEM REACHES 50 PERCENT OF THE DESIGN CAPACITY. USE OF THE SYSTEM SHOULD BE DISCONTINUED UNTIL APPROPRIATE MEASURES CAN BE INITIATED TO CLEAN THE STRUCTURE. PREFABRICATED SYSTEMS SHOULD ALSO UTILIZE THIS CRITERION, UNLESS THE MANUFACTURER HAS ALTERNATE SPECIFICATIONS.
- UPON REMOVAL OF THE SOLIDS, INSPECT THE STRUCTURE. REPAIR THE STRUCTURE AS NEEDED OR CONSTRUCT A NEW SYSTEM.
- DISPOSE OF ALL CONCRETE IN A LEGAL MANNER. REUSE THE MATERIAL ON SITE, RECYCLE, OR HAUL THE MATERIAL TO AN APPROVED CONSTRUCTION/DEMOLITION LANDFILL SITE. RECYCLING OF MATERIAL IS ENCOURAGED. THE WASTE MATERIAL CAN BE USED FOR MULTIPLE APPLICATIONS INCLUDING BUT NOT LIMITED TO ROADBEDS AND BUILDING. THE AVAILABILITY FOR RECYCLING SHOULD BE CHECKED LOCALLY.
- THE PLASTIC LINER SHOULD BE REPLACED AFTER EVERY CLEANING; THE REMOVAL OF MATERIAL WILL USUALLY DAMAGE THE LINING.
- THE CONCRETE WASHOUT SYSTEM SHOULD BE REPAIRED OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE.
- CONCRETE WASHOUT SYSTEMS ARE DESIGNED TO PROMOTE EVAPORATION. HOWEVER, IF THE LIQUIDS DO NOT EVAPORATE AND THE SYSTEM IS NEAR CAPACITY IT MAY BE NECESSARY TO VACUUM OR REMOVE THE LIQUIDS AND DISPOSE OF THEM IN AN ACCEPTABLE METHOD. DISPOSAL MAY BE ALLOWED AT THE LOCAL SANITARY SEWER AUTHORITY PROVIDED THEIR NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMITS ALLOW FOR ACCEPTANCE OF THIS MATERIAL. ANOTHER OPTION WOULD BE TO UTILIZE A SECONDARY CONTAINMENT SYSTEM OR BASIN FOR FURTHER DEWATERING.
- PREFABRICATED UNITS ARE OFTEN PUMPED AND THE COMPANY SUPPLYING THE UNIT PROVIDES THIS SERVICE.
- INSPECT CONSTRUCTION ACTIVITIES ON A REGULAR BASIS TO ENSURE SUPPLIERS, CONTRACTORS, AND OTHERS ARE UTILIZING DESIGNATED WASHOUT AREAS. IF CONCRETE WASTE IS BEING DISPOSED OF IMPROPERLY, IDENTIFY THE VIOLATORS AND TAKE APPROPRIATE ACTION.
- WHEN CONCRETE WASHOUT SYSTEMS ARE NO LONGER REQUIRED, THE CONCRETE WASHOUT SYSTEMS SHALL BE CLOSED, DISPOSE OF ALL HARDENED CONCRETE AND OTHER MATERIALS USED TO CONSTRUCT THE SYSTEM.
- HOLES, DEPRESSIONS AND OTHER LAND DISTURBANCES ASSOCIATED WITH THE SYSTEM SHOULD BE BACKFILLED, GRADED, AND STABILIZED.

**RIP-RAP - PIPE OUTLET TO CHANNEL**





**NOTES:**

- The filter fabric shall meet the requirements in material specification 592 GEOTEXTILE Table 1 or 2, Class I, II or III.
- The rock riprap shall meet the IDOT requirements for the following gradation RR-3.
- The riprap shall be placed according to construction specification 61 LOOSE ROCK RIPRAP. The rock may be equipment placed.

REFERENCE	Project	Date	STANDARD DWG. NO.
Designed	_____	_____	IL-611
Checked	_____	_____	SHEET 1 OF 1
Approved	_____	_____	DATE 8-18-94

**MAINTENANCE**  
INSPECT RIPRAP OUTLET STRUCTURES AFTER HEAVY RAINS TO SEE IF ANY EROSION AROUND OR BELOW THE RIPRAP HAS TAKEN PLACE OR IF STONES HAVE BEEN DISLODGED. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE.

**STABILIZED CONSTRUCTION ENTRANCE PLAN**




- NOTES:**
- Filter fabric shall meet the requirements of material specification 592 GEOTEXTILE, Table 1 or 2, Class I, II or IV and shall be placed over the cleared area prior to the placing of rock.
  - Rock or reclaimed concrete shall meet one of the following IDOT coarse aggregate gradation, CA-1, CA-2, CA-3 or CA-4 and be placed according to construction specification 25 ROCKFILL using placement Method 1 and Class III compaction.
  - Any drainage facilities required because of washing shall be constructed according to manufacturer's specifications.
  - If wash racks are used they shall be installed according to the manufacturer's specifications.

REFERENCE	Project	Date	STANDARD DWG. NO.
Designed	_____	_____	IL-630
Checked	_____	_____	SHEET 1 OF 2
Approved	_____	_____	DATE 8-18-94


**STABILIZED CONSTRUCTION ENTRANCE PLAN**

- MAINTENANCE:**
- INSPECT DAILY.
  - RESHAPE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
  - TOP DRESS WITH CLEAN AGGREGATE AS NEEDED.
  - IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS.
  - FLUSHING SHOULD ONLY BE USED IF THE WATER CAN BE CONVEYED INTO A SEDIMENT TRAP OR BASIN.



REFERENCE	Project	Date	STANDARD DWG. NO.
Designed	_____	_____	IL-630
Checked	_____	_____	SHEET 2 OF 2
Approved	_____	_____	DATE 8-18-94

**TEMPORARY SOIL STOCKPILE DETAIL**



- NOTES:**
- Stockpile slopes should be based on angle of repose of the soil material to avoid potential sloughing of the slope.
  - Soil stockpile to be stabilized in accordance with practical standards.
  - Do not locate stockpile within overlaid drainage flow path, designated floodways, drip line or over the root crown of adjacent trees.
  - Provisions for sediment control practices may be required along haul roads and entrance/exit locations for access the soil stockpile that can create flow path for stormwater runoff.
  - Installation of benches, terraces, or slope interrupters should be considered.
  - Avoid building soil stockpiles on impervious surfaces.
  - Linear sediment trap surrounding the stockpile base may be used to control sediment.

REFERENCE	Project	Date	STANDARD DWG. NO.
Designed	_____	_____	IUM-627
Checked	_____	_____	SHEET 1 OF 1
Approved	_____	_____	DATE JANUARY 2017

**811**  
Know what's below.  
Call before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:  
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.

**ATWELL**  
www.atwell-group.com  
866.850.4200  
3100 W. WASHINGTON ST. SUITE 200  
ANN ARBOR, MI 48104  
734.994.4000

ROCHELLE II SOLAR PROJECT  
SOIL EROSION AND SEDIMENTATION CONTROL NOTES AND DETAILS  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS

**Green Power**

CLIENT: \_\_\_\_\_  
DATE: 04/14/2021


REVISIONS

REV A	ISSUED FOR REVIEW
REV B	ISSUED FOR REVIEW
REV C	ISSUED FOR VARIANCE
REV D	ISSUED FOR VARIANCE

SCALE: 0 XX XXX  
AS NOTED

DR. SPB | CH. SPB  
P.M. JFC  
BOOK: --  
JOB: 20004665  
SHEET NO. C-102

CAD FILE: 20004665-C-102.DWG



**PROPOSED SITE PLAN**  
SCALE: 1" = 100'-0"




Know what's below.

Call before you dig.  
THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE MANNER ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCURRED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE: CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES OR OF ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.



ROCHELLE II SOLAR PROJECT  
PROPOSED SITE PLAN  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS

REV	DATE	ISSUED FOR
A	04/14/2021	ISSUED FOR REVIEW
B		ISSUED FOR REVIEW
C		ISSUED FOR VARIANCE
D		ISSUED FOR VARIANCE

NO.	DATE	REVISIONS


SCALE: 0 50 100  
1" = 100'-0"  
DR. SPB | CH. SPB  
P.M. JFC  
BOOK --  
JOB 20004665  
SHEET NO. C-200

S:\20004665 - ROCHELLE II SOLAR PROJECT\PLANS\20004665-C-200.DWG 4/14/2021 8:28 AM SEAN BAILES

CAD FILE: 20004665-C-200.DWG







**SOIL LEGEND**

SOIL TYPE	SOIL NAME
152A	Drummer silty clay loam 0 to 2 percent slopes
198A	Elburn silt loam 0 to 2 percent slopes
199A	Piano silt loam 0 to 2 percent slopes
411B	Ashdale silt loam 2 to 5 percent slopes
488A	Hoagpole loam 0 to 2 percent slopes
3074A	Roadford silt loam 0 to 2 percent slopes

**GRADING, DRAINAGE AND UTILITY NOTES**

- UNDERGROUND UTILITIES WERE COMPILED FROM AVAILABLE RECORD PLANS OF UTILITY COMPANIES AND PUBLIC AGENCIES, ARE APPROXIMATE AND ASSUMED. BEFORE COMMENCING SITE WORK IN ANY AREA, CONTACT "811" OR EQUIVALENT AND THE OWNER TO ACCURATELY LOCATE UNDERGROUND UTILITIES. ANY DAMAGE TO EXISTING UTILITIES OR STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY. NO EXCAVATION SHALL BE DONE UNTIL UTILITY COMPANIES AND THE OWNER ARE PROPERLY NOTIFIED IN ADVANCE.
- ALL SITE WORK SHALL MEET OR EXCEED THE SITE WORK SPECIFICATIONS TO BE PREPARED FOR THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED, THE CONTRACTOR SHALL NOTIFY THE OWNER AND THE ENGINEER PRIOR TO INSTALLATION OF ANY PORTION OF THE SITE WORK WHICH WOULD BE AFFECTED.
- ALL WORK PERFORMED AND ALL MATERIALS FURNISHED SHALL CONFORM WITH THE LINES, GRADES AND OTHER SPECIFIC REQUIREMENTS OR SPECIFICATIONS FOR THE PROJECT AS SHOWN ON THE PLANS.
- THE CONTRACTOR SHALL VERIFY EXISTING GRADES IN THE FIELD AND REPORT ANY DISCREPANCIES IMMEDIATELY TO THE ENGINEER. THE CONTRACTOR SHALL MAKE ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENT OF GAS, ELECTRIC, TELEPHONE AND ANY OTHER PRIVATE UTILITIES BY THE UTILITY COMPANIES, AS REQUIRED. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED TO THE OWNER AND ENGINEER FOR RESOLUTION.
- NO DETENTION AND/OR RETENTION AREAS ARE REQUIRED.
- CONTRACTOR SHALL PROTECT ALL UNDERGROUND DRAINAGE, SEWER AND UTILITY FACILITIES FROM EXCESSIVE VEHICULAR LOADS DURING CONSTRUCTION. ANY DAMAGE TO THESE FACILITIES RESULTING FROM CONSTRUCTION LOADS WILL BE RESTORED TO ORIGINAL CONDITION.
- THE CONTRACTOR SHALL REMOVE ALL NON-BIODEGRADABLE EROSION CONTROL BARRIERS AFTER RE-VEGETATION OF DISTURBED AREAS.
- IF IT IS DETERMINED THAT WETLANDS ARE PRESENT ONSITE, THEY ARE TO REMAIN UNDISTURBED. NO ENCROACHMENT PERMITTED UNLESS NOTED ON PLANS.
- PITCH EVENLY BETWEEN SPOT GRADES.
- THE CONTRACTOR SHALL SCHEDULE HIS WORK TO ALLOW THE FINISHED SUBGRADE ELEVATIONS TO DRAIN PROPERLY WITHOUT PONDING. SPECIFICALLY, ALLOW WATER TO ESCAPE WHERE PROPOSED CURB MAY RETAIN RUNOFF PRIOR TO APPLICATION OF THE FINISH SUBGRADE AND/OR SURFACE PAVING. PROVIDE TEMPORARY POSITIVE DRAINAGE AS REQUIRED.
- EXISTING SITE SURFACE DRAINAGE PATTERNS WILL BE MAINTAINED.
- ACCESS DRIVES AND ARRAY ARE INTENDED TO BE INSTALLED AT EXISTING GRADE TO MAINTAIN EXISTING FLOW PATTERNS AND NOT CREATE A BLOCKAGE (NO MASS GRADING IS REQUIRED). MINOR GRADING MAY BE NECESSARY AT INVERTER SKID LOCATIONS. SUBSTATION TO BE DESIGNED BY SUBSTATION EPC.
- IF DRAIN TILES ARE ENCOUNTERED DURING CONSTRUCTION, CONTRACTOR SHALL RELOCATE/REPAIR AS NECESSARY TO MAINTAIN THEIR FUNCTIONALITY.
- STORM WATER MANAGEMENT. BEST MANAGEMENT PRACTICES SHALL BE EMPLOYED TO MINIMIZE EROSION AND SEDIMENTATION DURING CONSTRUCTION OF THE SOLAR FARM.

**SITE NOTES**

- TO MINIMIZE SOIL DISTURBANCE AND IMPACTS TO GROUNDWATER INFILTRATION, SOLAR PANELS SHALL HAVE DRIVEN PILE FOUNDATIONS OR GROUND SCREW ANCHORS. IF THE FACILITY IS WITHIN 1,000 FEET OF AN INHABITED RESIDENCE, PILE FOUNDATIONS SHALL BE INSTALLED WITH A HYDRAULIC PILE HAMMER OR SIMILAR SOUND ATTENUATING PROCESS (AS COMPARED TO AN IMPACT-DRIVEN HAMMER) UNLESS NOT FEASIBLE DUE TO ENVIRONMENTAL OR GEOLOGIC CONDITIONS.
- ALL REQUIREMENTS FOR SAFETY, ABANDONMENT, AND DECOMMISSIONING (INCLUDING BONDING) OUTLINED IN THE CITY OF ROCHELLE ORDINANCE, LATEST ADDENDUM, SHALL BE MET.

**STORMWATER MANAGEMENT CALCS.**

SITE DATA TABLE	
TOTAL PROPERTY AREA (ACRES)	91.4
TOTAL DEVELOPED (FENCED) AREA (ACRES)	62.8
PROPOSED NEW IMPERVIOUS AREA (ACRES)	2.6
PERCENT IMPERVIOUS AREA	2.8%

- PROPOSED IMPERVIOUS AREA INCLUDES THE SUBSTATION, CHIP AND SEAL COATED ACCESS DRIVES, EQUIPMENT PADS, FENCE POSTS, AND ARRAY PILES.
- SINCE PROPOSED RUNOFF FROM SITE IS LESS THAN EXISTING RUNOFF, NO STORMWATER DETENTION IS NECESSARY; HOWEVER, EROSION AND SEDIMENT CONTROLS ARE REQUIRED SINCE THE DISTURBED AREA IS GREATER THAN 1 ACRE.

**PRELIMINARY STORMWATER SUMMARY**

SITE HYDROLOGIC SOIL RATING:	B/D 95.5%
	B 4.5%
TYPICAL LAND USE:	CROP, SMALL GRAIN
CN FOR EXISTING SITE:	86
PROPOSED COVER:	GRAVEL & MEADOW
CN FOR PROPOSED PROJECT AREA:	79
EXISTING Q100 =	150 CFS
EXISTING V100 =	29.2 AC-FT
PROPOSED Q100 =	130 CFS
PROPOSED V100 =	25.1 AC-FT

- HYDROLOGIC ANALYSIS PERFORMED USING SCS METHOD WITHIN HYDRAFLOW HYDROGRAPHS EXTENSION FOR AUTOCAD CIVIL3D.
- THE DRAINAGE AREA WILL NOT BE ALTERED BETWEEN THE EXISTING CONDITIONS AND THE PROPOSED CONDITIONS.
- THE DIFFERENCE BETWEEN THE TIME OF CONCENTRATION OF THE EXISTING CONDITIONS AND THE PROPOSED CONDITIONS WILL BE NEGLIGIBLE.

**HYDROLOGIC SUMMARY TABLE**

EXISTING FARMED CONDITION	CN	AC
TOTAL PARCEL AREA		91.4
DEVELOPED (FENCED) AREA		62.5
HSG A - SMALL GRAIN - STRAIGHT ROW - GOOD	63	0.0
HSG B - SMALL GRAIN - STRAIGHT ROW - GOOD	75	2.8
HSG C - SMALL GRAIN - STRAIGHT ROW - GOOD	83	0.0
HSG D - SMALL GRAIN - STRAIGHT ROW - GOOD	87	60.0
<b>WEIGHTED CN - EXISTING FARMED CONDITION</b>		<b>87</b>
<b>PROPOSED SOLAR FARM</b>		
	UNIT	QUANT
PAVED ENTRANCE	1	5379 SF
CHIP AND SEAL COATED ACCESS DRIVES	1	58109 SF
SUBSTATION AREA	1	126394 SF
INVERTER AREA	2000 SF	4
<b>TOTAL IMPERVIOUS AREA</b>		<b>197,882 SF</b>
	CN	AC
IMPERVIOUS AREA (CALCULATED ABOVE)	98	4.5
HSG A - MEADOW - GOOD (NOT USED - SEE NOTE*)	30	
HSG B - MEADOW - GOOD*	58	0.0
HSG C - MEADOW - GOOD*	71	2.8
HSG D - MEADOW - GOOD*	78	55.2
<b>WEIGHTED CN - GRASSY ARRAY (MEADOW) W/ IMPERVIOUS AREA</b>		<b>79</b>
* USING NEXT HIGHER HSG TO ACCOUNT FOR CONSTRUCTION		
<b>SUMMARY</b>		
TOTAL PARCEL AREA	AC	91.4
TOTAL FENCED AREA	AC	62.5
PROPOSED IMPERVIOUS AREA	AC	4.5
IMPERVIOUS AREA COVERAGE PERCENTAGE		4.9%
RUNOFF CN - EXISTING		87
RUNOFF - PEAK FLOW Q100 - EXISTING	CFS	150
RUNOFF - VOLUME V100 - EXISTING	AC-FT	29.2
RUNOFF CN - PROPOSED		79
RUNOFF - PEAK FLOW Q100 - PROPOSED	CFS	130
RUNOFF - VOLUME V100 - PROPOSED	AC-FT	25.1

Know what's below.  
Call before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE CONTRACTOR OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE: CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.

866.850.4200 www.atwell-group.com

3 WORKINGMEN CENTER BLVD  
ANN ARBOR, MI 48104  
PH: 734.934.4000


ROCHELLE II SOLAR PROJECT  
GRADING AND DRAINAGE NOTES, AND TABLES  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS

CLIENT	
DATE	04/14/2021
REV A	ISSUED FOR REVIEW
REV B	ISSUED FOR REVIEW
REV C	ISSUED FOR VARIANCE
REV D	ISSUED FOR VARIANCE
REVISIONS	
SCALE	X XX XXX
AS NOTED	
DR. SPB	CH. SPB
P.M. JFC	
BOOK	--
JOB	20004665
SHEET NO.	C-301

S:\20004665 - ENCL - ROCHELLE II SOLAR PROJECT\DWG\20004665-C-301.DWG 1/17/2021 10:35 AM SEAN BAKER

CAD FILE: 20004665-C-301.DWG







Common Name	Species Name	Height (feet)	Deciduous/Evergreen
<b>Shrubs</b>			
Ninebark	<i>Physocarpus opulifolius</i>	8	Deciduous
Silly dogwood	<i>Cornus amomum</i>	8	Deciduous
Winterberry	<i>Ilex verticillata</i>	8	Deciduous
Black-haw	<i>Viburnum prunifolium</i>	15	Deciduous
Southern arrowwood	<i>Viburnum dentatum</i>	8	Deciduous
Inkberry	<i>Ilex glabra</i>	8	Evergreen
<b>Trees</b>			
Black Gum	<i>Nyssa sylvatica</i>	50	Deciduous
Swamp white oak	<i>Quercus bicolor</i>	60	Deciduous
Shingle oak	<i>Quercus imbricaria</i>	60	Deciduous
Lacebark elm	<i>Ulmus parvifolia</i>	50	Deciduous
Eastern white cedar	<i>Thuja occidentalis</i>	20-40	Evergreen
Eastern white pine	<i>Pinus strobus</i>	80	Evergreen
Eastern hemlock	<i>Tsuga canadensis</i>	70	Evergreen

**PLANTING NOTES**

- ALL STOCKPILE AREAS SHALL BE LOCATED WITHIN LIMIT OF WORK LINE AND STABILIZED TO PREVENT EROSION.
- ALL DEBRIS GENERATED DURING SITE PREPARATION ACTIVITIES SHALL BE LEGALLY DISPOSED OFF SITE.
- PROVIDE CRIBBING AS NECESSARY TO PROTECT EXISTING UTILITY LINES DURING CONSTRUCTION.
- PLANTING SEED SHALL BE SOWN IN SEASONAL CONDITIONS AS APPROPRIATE FOR GOOD SEED SURVIVAL, OR AT SUCH TIMES AS APPROVED BY THE OWNER.
- PROTECT NEWLY TOPSOILED, GRADED AND/OR SEEDED AREAS FROM TRAFFIC AND EROSION. KEEP AREAS FREE OF TRASH AND DEBRIS RESULTING FROM LANDSCAPE CONTRACTOR OPERATIONS.
- REPAIR AND RE-ESTABLISH GRADES IN SETTLED, ERODED AND RUTTED AREAS TO THE SPECIFIED GRADE AND TOLERANCES.
- ALL PLANT MATERIAL SHALL CONFORM TO THE MINIMUM GUIDELINES ESTABLISHED BY THE AMERICAN STANDARD FOR NURSERY STOCK PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION.
- ANY PROPOSED SUBSTITUTIONS OF PLANT MATERIAL SHALL BE MADE WITH MATERIAL EQUIVALENT TO THE DESIRED MATERIAL IN OVERALL FORM, HEIGHT, BRANCHING HABIT, FLOWER, LEAF, COLOR, FRUIT AND CULTURE. PROPOSED SUBSTITUTIONS WILL ONLY BE CONSIDERED IF SUBMITTED WITH ENUMERATED REASONS WHY SUBSTITUTIONS ARE PROPOSED.
- THE LANDSCAPE CONTRACTOR SHALL CLEAN UP AND REMOVE ANY DEBRIS FROM THE SITE CAUSED BY THE LANDSCAPE CONTRACTOR.
- THIS PROJECT SHALL COMPLY WITH THE REQUIREMENTS AND PERFORMANCE STANDARDS IDENTIFIED BY THE CITY OF ROCHELLE PLANNING AND DEVELOPMENT STANDARDS FOR SOLAR FARMS. A VARIANCE FROM BERMING REQUIREMENTS IS BEING REQUESTED, SO NO BERMS ARE BEING SHOWN ON LANDSCAPING PLAN.
- REVEGETATION OF THE SOLAR ARRAY SHALL BE COMPLETED PER AN APPROVED VEGETATION PLAN OR LANDSCAPE PLAN PREPARED SPECIFICALLY FOR THE PROJECT SITE.
- VEGETATIVE COVER ALL AREAS OCCUPIED BY THE SOLAR FARM THAT ARE NOT UTILIZED FOR ACCESS TO OPERATE AND MAINTAIN THE SOLAR FARM SHALL BE PLANTED AND MAINTAINED WITH NATIVE GRASSES AND/OR OTHER VEGETATION FOR THE PURPOSE OF SOIL STABILIZATION OR OTHER METHOD AS RECOMMENDED BY THE PLANNING & ZONING COMMISSION AND/OR CITY COUNCIL.

THE SOLAR FARM OWNER/OPERATOR SHALL PROVIDE FOR WEED CONTROL IN A MANNER THAT PREVENTS THE SPREAD OF WEEDS ONTO AGRICULTURAL LAND AFFECTED BY THE CONSTRUCTION, OPERATION OR DECOMMISSION OF THE SOLAR FARM. SPRAYING SHALL BE DONE BY A PESTICIDE APPLICATOR THAT IS APPROPRIATELY LICENSED IN THE STATE OF ILLINOIS.

THE REQUIRED FENCE SURROUNDING THE SOLAR FARM SHALL BE MAINTAINED TO PREVENT THE GROWTH OF WOOD VEGETATION WITHIN AND ALONG THE FENCE.




**NOTES**

- THE LANDSCAPED BUFFER WILL BE COMPRISED OF TREES AND SHRUBS. TREES (2-INCH MIN. CALIPER @ PLANTING) WILL BE SPACED AT 30' INTERVALS, UNLESS NOTED OTHERWISE. AT LEAST 50% OF THE LENGTH OF THE LANDSCAPED BUFFER WILL BE PLANTED WITH SHRUBS (MINIMUM HEIGHT OF FOUR FEET @ PLANTING).
- ESTIMATED TOTAL OF 370 TREES, 760 SHRUBS, AND 6,800 FLOWER (NOT SHOWN) TO BE INCLUDED IN LANDSCAPED BUFFER.


**TREE PLANTING NOTES:**

- CROWN OF ROOT BALL SHALL BEAR SAME RELATION (OR SLIGHTLY ABOVE) TO FINISHED GRADE AS IT BORE TO PREVIOUS GRADE.
- DO NOT DAMAGE MAIN ROOTS OR DESTROY ROOT BALL WHEN INSTALLING TREE SUPPORT POSTS.
- REMOVE HOSE, POST, SAUCER AND WRAP AT END OF (1) ONE YEAR GUARANTEE PERIOD.

- 1"x2" WOOD BRACE NAILED TO POSTS FOR TREES OVER 3" CAL. POSTS SHALL BE WHITE CEDAR AS FOLLOWS:
- a) 2-2.5" DIA. POST (MINOR TREE); 4" POST HEIGHT
  - b) 3-3.5" DIA. POSTS (MAJOR TREES TO 3" CAL.); 5" POST HEIGHT
  - c) 3-3.5" DIA. POSTS (MAJOR TREES OVER 3" CAL.); 7" POST HEIGHT
- POST SHALL EXTEND 2'-6" MIN. BELOW FIN. GRADE.
- CUT ROPES AT TOP OF BALL, CUT AT LEAST 1/3 OF WIRES IN ANY TREE BALLED IN A WIRE BASKET.



**TREE PLANTING DETAIL**  
NOT TO SCALE



**NOTES:**

- CROWN OF ROOT MASS TO BE SLIGHTLY ABOVE FINISHED GRADE.
- FOR BARE ROOT SHRUBS: THIN BRANCHES AND FOLIAGE (ALL END TIPS) BY 1/3 RETAINING NORMAL PLANT SHAPE (BARE ROOT PLANTS ONLY).
- FOR CONTAINER SHRUBS: REMOVE POT, CHECK ROOT SYSTEM. IF THERE ARE ANY SIGNS OF BEING ROOT BOUND, SLASH ROOT MASS (WITH A SHARP KNIFE) VERTICALLY IN 4 EQUIDISTANT LOCATIONS.
- FOR BALLED AND BURLAPPED SHRUBS: REMOVE COLLAR ROPES AND TOP 1/3 OF BURLAP. CROWN OR SLOPE ALL SHRUB BEDS TO ASSURE A MIN. PITCH OF 3%.

**SHRUB PLANTING DETAIL**  
NOT TO SCALE

**811**  
Know what's below.  
Call before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:  
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.

**ATWELL**  
www.atwell-group.com  
666.850.4200  
3 WORKING STREET  
ANN ARBOR, MI 48104  
734.594.4000

ROCHELLE II SOLAR PROJECT  
LANDSCAPING NOTES AND DETAILS  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS

**enel** Green Power

CLIENT: \_\_\_\_\_  
DATE: 04/14/2021

REV A ISSUED FOR REVIEW  
REV B ISSUED FOR REVIEW  
REV C ISSUED FOR VARIANCE  
REV D ISSUED FOR VARIANCE

REVISIONS

SCALE: X XX XXX  
AS NOTED

DR. SPB | CH. SPB  
P.M. JFC  
BOOK: --  
JOB: 20004665  
SHEET NO. C-401

CAD FILE: 20004665-C-401.DWG

**811**  
Know what's below.  
Call before you dig.  
THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:  
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES OR ANY OTHER PERSONS.

COPYRIGHT © 2021 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.

**ATWELL**  
www.atwell-group.com  
666.850.4200  
3100 W. BIRCH, SUITE 200  
ANN ARBOR, MI 48104  
734.934.4000

ROCHELLE II SOLAR PROJECT  
STANDARD DETAILS  
PRELIMINARY SITE PLAN  
CITY OF ROCHELLE, ILLINOIS

**enel**  
Green Power

CLIENT: DATE: 04/14/2021


REV A ISSUED FOR REVIEW  
REV B ISSUED FOR REVIEW  
REV C ISSUED FOR VARIANCE  
REV D ISSUED FOR VARIANCE

REVISIONS

SCALE: 0 XX XXX  
AS NOTED

DR. SPB | CH. SPB  
P.M. JFC  
BOOK: --  
JOB: 20004665  
SHEET NO. C-500

PIPE ARCH DIMENSIONS		THICKNESS	DIMENSIONS					SLOPE (Approx.) (V:H)	BODY
SPAN	RISE		A	B	H	L	W		
17 (432)	13 (330)	0.064 (1.63)	7 (180)	9 (230)	6 (150)	19 (485)	30 (760)	1:2½	1 Pc.
21 (533)	15 (381)	0.064 (1.63)	7 (180)	10 (255)	6 (150)	23 (585)	36 (915)	1:2½	1 Pc.
24 (610)	18 (457)	0.064 (1.63)	8 (205)	12 (305)	6 (150)	28 (710)	42 (1,065 m)	1:2½	1 Pc.
28 (711)	20 (508)	0.079 (2.01)	9 (230)	14 (355)	6 (150)	32 (815)	48 (1,220 m)	1:2½	1 Pc.
35 (889)	24 (610)	0.079 (2.01)	10 (255)	16 (405)	6 (150)	39 (990)	60 (1,525 m)	1:2½	1 Pc.
42 (1067)	29 (737)	0.079 (2.01)	12 (305)	18 (460)	8 (205)	53 (1,370 m)	75 (1,905 m)	1:2½	1 Pc.
49 (1245)	33 (838)	0.109 (2.77)	13 (330)	21 (535)	9 (230)	46 (1,345 m)	85 (2,160 m)	1:2½	2 Pc.
57 (1448)	38 (965)	0.109 (2.77)	18 (460)	26 (660)	12 (305)	63 (1,600 m)	90 (2,285 m)	1:2½	2 Pc.
64 (1626)	43 (1092)	0.109 (2.77)	18 (460)	30 (760)	12 (305)	70 (1,780 m)	102 (2,590 m)	1:2½	2 Pc.
71 (1803)	47 (1194)	0.138 (3.51)	18 (460)	33 (840)	12 (305)	77 (1,955 m)	114 (2,895 m)	1:2½	3 Pc.
77 (1956)	52 (1321)	0.168 (4.27)	18 (460)	36 (915)	12 (305)	77 (1,955 m)	126 (3,200 m)	1:2	3 Pc.
83 (2108)	57 (1448)	0.168 (4.27)	18 (460)	39 (990)	12 (305)	77 (1,955 m)	138 (3,505 m)	1:2	3 Pc.




**NOTES**

For the 77x52 (1956x1321) and 83x57 (2108x1448) sizes, reinforced edges shall be supplemented with 2x2x¼ (51x51x6.4) stiffener angles. The angles shall be attached by ½ (M10) rivets or bolts.

Angle reinforcement shall be placed under the center panel seams on the 77x52 (1956x1321) and 83x57 (2108x1448) sizes.


All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).



**NOTES**

- Type 1 and 2 connection shall be used only with pipes with annular ends.
- Type 3 connection can be used with all pipe arch sizes and includes 12 (300) of the pipe length. The annular connector section shall be attached to the end section by rivets or bolts and shall be the same metal thickness as the end section. When coupling the type 3 end section to a pipe with helical ends, only the dimple type coupling band shall be used.
- Type 4 connection can be used with all pipe arch sizes. The end section band shall be either a dimple, huggar, or annular band and can be used with pipes having annular ends. For pipes having helical ends, only the dimple end section band will be allowed.

All dimensions are in inches (millimeters) unless otherwise shown.





**ALTERNATE STRAP CONNECTOR**  
(For Type 1 only)

DATE	REVISIONS
1-1-18	Renamed standard.
4-1-16	Revised THICKNESS values in table.

**METAL FLARED END SECTIONS FOR PIPE ARCHES**  
STANDARD 542406-03

Illinois Department of Transportation  
PASSED: January 1, 2018  
ENGINEER OF POLICY AND PROCEDURES  
APPROVED: January 1, 2018  
ENGINEER OF DESIGN AND ENVIRONMENT


**CONNECTIONS OF END SECTIONS**



**NOTES**

- CULVERT INSTALLATION SHALL CONFORM WITH IDOT STANDARD SPECIFICATIONS.
- MINIMIZE DISTURBANCE TO THE STREAM/DITCH DURING CULVERT INSTALLATION.
- WHEN SAND IS ENCOUNTERED, GEOTEXTILE FABRIC SHALL BE USED UNDER THE RIP-RAP AND PIPE BEDDING. R880R OR EQUIVALENT FABRIC SHALL BE USED.
- BEDDING MATERIAL SHALL BE COMPACTED TO 95% OF STANDARD PROCTOR VALUE.

**TYPICAL ACCESS ROAD CULVERT**  
NOT TO SCALE




**ELECTRIC CONDUIT TRENCH**  
NOT TO SCALE


SEE ELECTRICAL PLANS FOR MORE DETAILS.



**EMERGENCY CONTACT SIGN**  
NOT TO SCALE



**SUBSOIL EQUIPMENT FOUNDATION DETAIL**  
NOT TO SCALE



**ACCESS DRIVE CROSS SECTION**  
NOT TO SCALE

**NOTES**

- REMOVE TOPSOIL AND ALL UNSUITABLE MATERIAL AS REQUIRED AND REPLACE WITH GRAVEL.
- ACCESS DRIVES TO SLOPE IN THE DIRECTION OF THE EXISTING GRADE AT A MINIMUM OF 2.0% DRIVEWAY SHALL BE GRADED TO ALLOW STORMWATER TO SHEET ACROSS IT AND TO PREVENT PUDDING.
- FILTER FABRIC SHALL BE PLACED OVER THE CLEARED AREA PRIOR TO THE PLACING OF ROCK.